

INDUSTRIAL COMPONENT DATA

UTI 2,5-L 3076034 PHOENIX CONTACT Installation level terminal block, Screw connection, Cross section: 0.2 mm²

Brand: PHOENIX CONTACT | Manufacturer Part Number: UTI 2,5-L



Manufacturer	PHOENIX CONTACT
MPN / Reference	UTI 2,5-L
Catalog number	3076034
Category	Multi level installation terminal block
Minimum order	50 Pcs
Document ID	EO-662C282D32
Generated	2026-08-05

Product Overview

Installation level terminal block, Screw connection, Cross section: 0.2 mm²

Distribution floor terminal block, nominal voltage: 400 V, nominal current: 24 A, Screw connection, 1., 2. and 3rd floor, Dimensioning cross-section: 4 mm², cross-section: 0.2 mm² - 4 mm², mounting class: NS 35/7.5, NS 35/15, color: gray

STRUCTURED PRODUCT DATA

Technical Specifications

No structured technical attributes are currently available. Submit an RFQ for technical review.

Classification & Catalog Path

Catalog path	PHOENIX CONTACT > Modular TBs
--------------	-------------------------------

Additional Product Information

General

Note Assembly instructions:For secure fastening of the neutral busbar, supports must be set at the beginning and end of each terminal strip as well as every 20 cm on longer terminal strips.

Number of levels 3

Number of connections 2

Nominal cross section 4 mm²

Color gray

Insulating material PA

Flammability rating according to UL 94 V0

General

Maximum load current 30 A (with 4 mm² conductor cross section and 3-pos. terminal block)

24 A (with a 2.5 mm² conductor cross section)

Current carrying capacity of the neutral busbar 140 A

Rated surge voltage 4 kV
6 kV
Pollution degree 3
Overvoltage category III
Insulating material group I
Nominal current IN 24 A (with 4 mm² conductor cross section)
Maximum load current 30 A (with 4 mm² conductor cross section and 3-pos. terminal block)
Nominal voltage UN 400 V (phase conductor/phase conductor)
Open side panel ja
Shock protection test specification DIN EN 50274 (VDE 0660-514):2002-11
Back of the hand protection guaranteed
Finger protection guaranteed
Result of surge voltage test Test passed
Surge voltage test setpoint 7.3 kV
Result of power-frequency withstand voltage test Test passed
Power frequency withstand voltage setpoint 1.89 kV
Result of the test for mechanical stability of terminal points (5 x conductor connection) Test passed
Result of bending test Test passed
Bending test rotation speed 10 rpm
Bending test turns 135
Bending test conductor cross section/weight 0.2 mm² / 0.2 kg
2.5 mm² / 0.7 kg
4 mm² / 0.9 kg
Tensile tes...

REQUEST PRICE, AVAILABILITY & TECHNICAL REVIEW

Send PHOENIX CONTACT / UTI 2,5-L with the required quantity to info@electricaonline.com or use electricaonline.com/request-quote.

GLOBAL OFFICES

Germany: Lise-Meitner-Straße 13, 89081 Ulm | USA: 16225 Park Ten Pl #500, Houston, TX 77084 | UAE: HDS Business Centre Tower, Cluster M, 33rd Floor, JLT, Dubai

Catalog-generated document. Product names, marks and specifications belong to their respective owners. Verify safety-critical, compatibility and certification requirements against the manufacturer documentation before purchase or installation.